## 1000 kVA Connection to MIRA



The MIRA connection project required a partial and stage wise disconnection and reconnection of the customer distribution network, some of the units required to stay connected at all times.

GEW2 and WPD worked closely together to achieve correct switching sequences and allow installation of the new customer HV and LV equipment.

GEW2 assisted the customer in the design of a custom made brick WPD/Customer combined substation and a free standing package substation plinth.

## MIRA double switch



## **MIRA LV Cable Joints**

しってい 怒 したい かいってい 怒 したい 怒 しょうしゃ かいってい 怒 したい かいっかい





MIRA/WPD Combined Substation

## Scope:

- Supply and installation of 2 x customer circuit breakers
- Supply and installation of 1 x 1000 kVA package substation
- Supply and installation of 1 x customer LV board
- Supply and installation of customer LV cables
- Supply and installation of customer HV cables
- WPD coordination and hand over documentation
- 3 x HV terminations
- 14 x LV terminations
- On site customer LV cable design
- Customer HV and LV jointing
- Weekend work
- Customer/Sub-contractor coordination

GEW2 Ltd. Unit 4 – The Office Village Keypoint Nix's Hill Industrial Estate Alfreton, Derbyshire, DE557FQ Website: http://www.gew2.co.uk/ Contact: in facebook em@il

